

15th September 2027

Stephen Hamilton
66 Lower Court Road
Epsom
Surrey
KT19

Quotation Reference Number: T90032**Work to be carried out**

- Strip slates from main elevations back to original joist work.
- Supply and install 4x2 timber supports to loft area, where necessary.
- Remove courses of brickwork from rear chimney stack in order to reduce external height to below roof level.
- Supply and install any required additional Rockwool insulation to areas between floor joists in loft, ensuring that a total minimum depth of 300mm is achieved in order to comply with current building regulations.
- Supply and lay breathable under-slater's felt.
- Supply and lay premium grade gold battens to felt.
- Supply and install new aluminium slate soakers where necessary.
- Supply and install new over fascia vents where necessary.
- Supply and install new UPVC drip trays to perimeter of main elevations.
- Renew roof using Grade A natural slates; 500x250mm.
- Supply and install a mechanically dry fixed ridge system.
- Renew all lead surrounding chimney stack using code 4 lead, dressing in accordance with size.
- Re-point chimney stack where necessary using sand and cement mortar mix.
- Supply and erect scaffolding all around property.
- Provision of skips.
- All associated waste removed ensuring site left clear and tidy.
- All work guaranteed for 15 years (insurance backed for 10) and inclusive of LABC Certificate.

Materials & Labour	£	17,600.00
VAT (at current rate of 20%)	£	3,520.00
Total Cost	£	21,120.00

Full Employer's, Public & Liability Insurance held including gas gun usage, copies of certificates available upon request.
Payment due upon completion of works.

Kind Regards



Stephen Baker
Proprietor of South Thames Roofing Ltd

