

**Prepared For**

Stephen Hamilton
66 Lower Court Road
Epsom , Surrey KT198SN

Roofcraft of Surrey & London Ltd

Wesley House, Bull Hill
Leatherhead, Surrey KT227AH
Phone: 01372889698
Email: roofcraftofsurreyandlondon@gmail.com
Web: www.roofcraftofsurreyandlondon.co.uk

Quote # 341
Date 10/09/2026
Business / Tax # VAT NO 482927846

Description**Front & Rear New Roof Replacement**

Description of work to be carried out at the above address

1. Scaffolding & Access

- * Supply, erect and dismantle suitable scaffolding to the front, side and rear elevations of the property to provide safe access for all roofing and associated works.
- * Scaffolding to remain in place for the duration of the works as required.

2. Removal of Existing Roof Covering

- * Carefully strip and remove the existing slate roof covering to the front and rear roof elevations.
- * Remove and dispose of the existing roof battens and associated redundant roofing materials.
- * Clear all resulting waste from site and dispose of appropriately.

3. Investigation to Side Apex / Wall Tie

- * Following removal of the existing roof covering and once suitable access is available, investigate the dipped area of brickwork to the side elevation near the apex, as identified within the survey report.
- * Inspect the area to establish the condition of the brickwork and investigate the reported missing/defective wall tie.
- * Please note: This quotation allows for investigation/inspection only. Any remedial or structural works required to the brickwork, wall ties or surrounding area will be assessed following exposure and quoted separately before additional works are undertaken.

4. Brickwork Repairs Around Front Purlin

- * Carefully remove approximately 5-6 broken/damaged bricks surrounding the existing timber

purlin at the front of the property.

- * Supply and install approximately 5–6 new matching/suitable bricks around the purlin.

- * Bed and point new brickwork securely using suitable mortar and make good the immediate surrounding area.

5. Rear Chimney Stack Removal

- * Carefully dismantle and remove the existing leaning chimney stack located to the rear left-hand side of the property.

- * Reduce the chimney stack to below roof level.

- * Cap and make good the remaining chimney structure as required.

- * Supply and install one suitable ventilation brick to provide ventilation to the redundant chimney/flue.

- * Make good the roof area ready for the new roof covering.

6. New Roof Installation

Following stripping and preparation of the existing roof structure:

- * Supply and install new Tyvek breathable roofing membrane across the roof area.

- * Supply and install new 25mm x 38mm treated roofing battens.

- * Supply and install new eaves support trays as required.

- * Supply and install new GRP fibreglass valley system to the rear of the property.

- * Supply and install new dry verge system/caps to applicable verge edges.

- * Supply and install new dry ridge system.

- * Supply and install new Redland 49 concrete interlocking roof tiles, with colour to be selected by the customer from the available range.

- * Supply and install a new GRP bonding gutter where the new roof covering meets/adjoins the neighbouring property's existing roof.

- * Complete all necessary cutting, fixing and finishing works to provide a secure and weatherproof roof installation.

7. Completion & Waste Removal

- * Remove all roofing debris, old slate, battens, chimney materials, damaged bricks and other waste generated by the contracted works.

- * Leave the working areas reasonably clean and tidy upon completion.

- * Dismantle and remove scaffolding following completion of the works.

Quotation Includes

The quoted price includes all labour, materials, scaffolding and removal/disposal of waste required to complete the works described above.

Temporary repair to missing slate at rear of house roof before new roof is started to prevent further damages to loft or ceiling included.

New replacement is provided with a 10 year Guarantee

Important Exclusion – Side Apex / Wall Tie

The quoted price does not include any remedial works found to be necessary to the brickwork, wall ties or associated structure at the side elevation near the apex. This area will be investigated once access/exposure permits. Should additional repairs be required, the findings will be discussed with the customer and a separate quotation will be provided for approval prior to carrying out those additional works.

Subtotal	£17,945.00
Vat	£3,589.00
Total	£21,534.00

By signing this document, the customer agrees to the services and conditions outlined in this document.

Stephen Hamilton